







standard

CONDENSATE REMOVAL PUMP

Operated by an air conditioning cooling signal, the Standard peristaltic sets the standard for reliability. The remote install options means minimum future maintenance disruption.



6.5L/h max. flow




12m max. head (flow rate 6.5L/h)




- AC cooling signal operated
- Remote install possible
- Pumps contaminated water
- Can run dry



SUITABILITY







STANDARD SPECIFICATIONS

6.5L/h @ 12m head

12m

3m

47dB(A) 230V AC 50-60Hz 0.2A

Continuously

I appliance

8.5kW / 29,000Btu/h


40°C / 104°F

6mm ID

IPX1

n/a

n/a



	15								
	12						12m	max. he	ad
					:				
METRES HEAD	9				:				
					:				
	6				:				
					:				
	3								
		230V							
	0		3		6	9		2	15
		LITRES PER HOUR							

CHCCECTED V	TRA ACCECCORIEC						
SUGGESTED XTRA ACCESSORIES							
Description	Part No.						
Peri Spare Tube Kit	FP1282						
1 Amp Fuse	FP2620						
Tube To Soil Stack Adaptor	FP2038						
For more installation accessories take a look at our Aspen Xtra range							

	STANDARD OPTIONS	
Standard		FP2081/2



Standard pump • 2m Plug & play power cable

- Wall mounted bracket Fixing kit
- Install manual
- Download manual at aspenpumps.com





Max. flow

Max. head

Max. suction lift

Sound level@1m

Max. unit output

Max. water temp Inlet/outlet

IP Protection

Safety switch

Self priming

Thermal protection Fully potted

Power supply Rated

Class







